BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Construction of Sheltar and Power Conection for Shredder in Behind Police Station

Agency:-M/s N RAMA MURTHY ( )

SCHEDULE-B

Sl No	App Qty	Description of work	Approved Rates of M/s N RAMA MURTHY ( )		
			Unit	Rate in Figures	Rate in Words
1	16.20	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete asper specifications	Cum	190.00	Rupees One Hundred Ninety Only
2	5.40	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates at 0.85cum and fine aggregates at 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	4839.00	Rupees Four Thousand Eight Hundred Thirty Nine Only
3	9.74	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per/ specifications.	Cum	4163.00	Rupees Four Thousand One Hundred Sixty Three Only
4	4.18	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	4976.00	Rupees Four Thousand Nine Hundred Seventy Six Only
5	7.38	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete Cum (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , mainand secondary beams with all lead and lifts etc., complete (exclusiveof cost of steel and fabrication charges.)	Cum	5845.00	Rupees Five Thousand Eight Hundred Forty Five Only
6	0.99	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	MT	56377.00	Rupees Fifty Six Thousand Three Hundred Seventy Seven Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

7/12/1

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	App Qty	Description of work	Approved Rates of M/s N RAMA MURTHY ( )		
			Unit	Rate in Figures	Rate in Words
7	1370.00	Fabricating, supplying & erecting M.S. angular Truss of span upto 10m. The bottom & top member is provided with 50x50x6mm double equal angles, welded back to back and in between top & bottom line, in areas of mid section is provided with 50x50x6mm equal single angle for vertical and inclined members and at supporting ends 40x40x5mm single angle is provided. All the members are welded together with 6mm gusset plate as per Drawing No.CBS/ SD/K-Mantap/9/MND/97. The entire truss is anchored in RCC column by using 4 Nos. of M.S. anchor bolts at each support, with 10mm thick base plate and shoe plate.The work includes cutting, straightening, placing in position of M.S angle and wleding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of all materials, labour charges, & hire charges of machineries for cutting, welding, grinding & erection equipments, etc., complete as per specification.	Kgs	116.00	Rupees One Hundred Sixteen Only
8	122.30	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvolume iron Trapezoidal profiled sheet of approved make 1060 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses.	Sqm	766.00	Rupees Seven Hundred Sixty Six Only
9	105.00	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications.	Kg	78.00	Rupees Seventy Eight Only
10	9.00	Providing and fixing 1mm thick M.S. sheet garage door with frame and diagonal braces of size 40x40x6 mm angle Iron, 3.15mm thick M.S. Gusset plates at the junctions and corners, with handles, stoppers and locking arrangements etc., including applying a priming coat of red lead paint cost of materials, labour, HOM of machinery complete as per specifications. Double leaf door of size 2.4x2.4m.	Sqm	2319.00	Rupees Two Thousand Three Hundred Nineteen Only
11	50.00	Open conduit System: Supplying heavy gauge PVC conduit pipe .....dia confirming to IS 2509 with suitable size bends, plugs in case of RCC ceiling and RCC wall stone structure or rawl plugs in case of brick walls and cement plastering damaged portion using heavy gauge saddles at an interval of 700mm using WF screws.a) 19/25 mm dia 2mm thick	mtr	51.00	Rupees Fifty One Only
12	2.00	Supplying and flush mounting teak wooden box without front plank, made of not less than 15mm thick wood, after due groove cutting, necessary masonry patch work complete. d)8"x6"x3"(203x152x76mm)	each	68.00	Rupees Sixty Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

	App Qty	Description of work	Approved Rates of M/s N RAMA MURTHY ( )		
			Unit	Rate in Figures	Rate in Words
13	1.00	Point wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit/casing caping using Copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixied on the exisiting plastic sheet /gang box, the pther end of the wires shall be terminated with sufficient loose length in a wood/PVC round block.complete for each outlet. I. Point wiring using class A materials a) Short point upto 3Mtr from tapping point to out let via switch	each	163.00	Rupees One Hundred Sixty Three Only
14	1.00	Supplying 6A flush/projected type socket and a 6 amps flush/ projected type SP switch either surface/flush mounting in a exisiting gang box or in a 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required. b) 6Amps 3/5 way	each	119.00	Rupees One Hundred Nineteen Only
15	80.00	Wiring for lighting/power circuit using one of FLRS PVC insulated 1100v grade, multis and CopperWITH LOW conductor single core cable in open or consealed system of wiring.I Group A Materials.a) 1.5 sqmm	mtr	12.00	Rupees Twelve Only
16	2.00	Supplying and fixing pbbc bakelight stright or slant batton holderand wiring within 60v/230volts lamp group A	each	83.00	Rupees Eighty Three Only
17	2.00	Supply patti type tube light fittings of 4'-28 watts fluorescent tube fittings made out of Ms sheet ans stove enameled with low loss open construction copper wound ferromagnetic ballast starter ,locking type brass contact holders mounted on double fold type sheet base fully wired for use on 230 volts AC supply including t5 lamp	each	656.00	Rupees Six Hundred Fifty Six Only
18	2.00	FSUPPLING OF 2 PIN/4PIN 18W CFL LAMP	each	113.00	Rupees One Hundred Thirteen Only
19	2.00	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides with plank made out of not more than 2 pices and fixing the same to the wall using tapered inverted woode plug screws etc., a) 20"x20"2.5"	each	283.00	Rupees Two Hundred Eighty Three Only
20	6.00	Supplying and fixing of Procelain fuse channel with cut out on exisiting wooden/panel using necessary nuts, bolts and washers etc., complete.a) 32Amps champter 5	each	169.00	Rupees One Hundred Sixty Nine Only
21	1.00	Supply of an load charge over switches 4poles 415v 50Hz A.C supply with AC23A duty a) up to 63amps Groups A	each	4589.00	Rupees Four Thousand Five Hundred Eighty Nin Only
22	1.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and C type curve indicator ON/OFF Energy cross 3 with short circuit breaking capacity of 10K and complete wiring as required. e)5-32amps TPN .	each	1816.00	Rupees One Thousand Eight Hundred Sixteen Only
23	1.00	Supplying fixing and wiring Electronic 10 to 40 amps Three phase 4wire class -1 Accuracy energy meter Group A	each	4596.00	Rupees Four Thousand Five Hundred Ninety Si Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

	App Qty	Description of work	Approved Rates of M/s N RAMA MURTHY ( )		
			Unit	Rate in Figures	Rate in Words
24	2.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipments on the meter board using 40mm dia 2.90 thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proprotion of salt and charcoal 150mm alround the pipe to complete depth. the connection form the pipe to the conduit etc, is to be established through GI wire of size as oer ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and checknuts etc, the pipe shall have 16 through holes of 12mm dia.	each	2558.00	Rupees Two Thousand Five Hundred Fifty Eight Only
25	15.00	Supplying and running of GI/Copper strips for grounding connections using necessary fixing material as required GI strip 25x3mm	mtr	72.00	Rupees Seventy Two Only
26	25.00	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanished, steel wire/steel tap armoured cable with PVC outer sheating 1.1 KV class.I. Class 'A' PVC Cable.d) 4 core 16 sqmm	mtr	132.00	Rupees One Hundred Thirty Two Only
27	20.00	Labour charges for lying of 1.1 KV class UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall /on pole as required. I. In existing trench/duct.a) 6 sqmm to 16 sqmm	mtr	15.00	Rupees Fifteen Only
28	1.00	Supplying exhaust fan of 1440 RPM of 300mm (12") sizewith bracket blades complete for light duty suitable to operate on 230V 50Hz. AC Supply, as per the directions of the Engineer-in-charge of the work.	Nos	1595.00	Rupees One Thousand Five Hundred Ninety Five Only
29	20.00	Digging of trench of 0.6 m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc.,complete.	mtr	110.00	Rupees One Hundred Ten Only
30	8.00	Supplying and fixing of class A (medium duty) GI pipe of wall thick ness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class. a) 40mm	mtr	324.00	Rupees Three Hundred Twenty Four Only
31	1.00	Supplying &fixing L.T.cast iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers ect.b) 16 Sqmm	each	263.00	Rupees Two Hundred Sixty Three Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

7/x/18

Contractor

Executive Engineer
Project Division
Yelahanka Zone